



LSP SERVICES • CIVIL ENGINEERING • ASSESSMENT • PERMITTING • REMEDIATION • CONSTRUCTION MANAGEMENT

October 2, 2012

Ms. Kimberly Tisa USEPA New England, Region 1 5 Post Office Square - Suite 100 Boston, Massachusetts 02109-3912

Risk-Based Approach Removal of PCB Containing Caulk Re:

> **Commercial Office Building** 130 Bishop Allen Drive Cambridge, Massachusetts

Lightship Engineering Ref. No. 532.72.2

Dear Ms. Tisa:

On behalf of Intercontinental Real Estate Corporation, Lightship Engineering, LLC, submits to the United States Environmental Protection Agency, a Risk-Based Approach in connection with the above-referenced Site:

If you have any questions regarding the Risk-Based Approach, please contact either Brian LaPierre or Timothy Condon at (508) 830-3344, extensions 130 and 120, respectively.

Very truly yours,

Lightship Engineering, LLC

Brian LaPierre, P.E.

Senior Project Manager

Timothy Condon, P.E., LSP

President


Mr. Scott Kelly, Intercontinental Real Estate Corporation cc:





RISK-BASED APPROACH REMOVAL OF PCB CONTAINING CHALK

Commercial Office Building 130 Bishop Allen Drive Cambridge, Massachusetts



(Lightship Engineering Project No. 532.72.2)

October 2, 2012

Prepared for:

Intercontinental Real Estate Corporation 1270 Soldiers Field Road Boston, Massachusetts 02135-1003 Prepared by:

Lightship Engineering, LLC 39 Industrial Park Road, Unit C Plymouth, Massachusetts, 02360





TABLE OF CONTENTS

1.0	INTE	RODUCTION	1-1
	1.1	CONCEPTUAL SITE MODEL	1-1
	1.2	SUMMARY OF PROPOSED ABATEMENT ACTIVITIES	1-2
2.0	BUII	DING MATERIALS CHARACTERIZATION	2-1
	2.1	CHARACTERIZATION SAMPLE COLLECTION	
		2.1.1 Sample Collection Methods	2-1
		2.1.2 <u>Laboratory Analytical Results</u>	2-2
	2.2	DATA USEABILITY ASSESSMENT	2-2
3.0	PCB	CAULKING ABATEMENT ACTIVITIES	3-1
	3.1	ABATEMENT PLAN	3-1
	3.2	CONTAINMENT STRUCTURES	3-2
	3.3	STORAGE AND DISPOSAL	
	3.4	ABATEMENT SCHEDULE	
	3.5	SITE RESTORATION	
	3.6	RECORDKEEPING AND DOCUMENTATION	
	8.18	3.6.1 Field Notes	
		3.6.2 Photographs	3-3
		3.6.3 Transport and Disposal Documentation	
		3.6.4 Abatement Completion Report	3-3
4.0	LIM	ITATIONS	4-1





LIST OF APPENDICES

APPENDIX A FIGURES

Figure 1-1 Site Locus Map

Figure 2-1 Examples of Caulking Materials

Figure 2-2 Examples of Caulking in Contact with

Building Materials

APPENDIX B ANALYTICAL SUMMARY TABLE

Table 1-1 PCB Concentrations in Caulking

APPENDIX C LABORATORY ANALYTICAL DATA PACKAGES

APPENDIX D CONCRETE SEALANT TECHNICAL DATA SHEET





1.0 INTRODUCTION

On behalf of Intercontinental Real Estate Corporation ("Intercontinental"), Lightship Engineering, LLC ("Lightship Engineering") has prepared this *Risk-Based Approach* in connection with the investigation and proposed abatement of window caulking containing polychlorinated biphenyls ("PCBs") at the commercial building located at 130 Bishop Allen Drive in Cambridge, Massachusetts (the "Site"). A Site Locus Map is provided as Figure 1-1, Appendix A.

1.1 CONCEPTUAL SITE MODEL

The Site building is a five-story commercial building with a basement. The basement level is used for storage and building operation and/or maintenance activities. As part of a building renovation plan that includes replacement of existing windows, samples of window and door caulking were collected from select locations that were submitted to an analytical laboratory for PCBs (Method 8082, Extraction Method 3540C) analysis. Total PCB concentrations were reported between non-detect (less than one milligram per kilogram ["mg/kg"]) to 3,750 mg/kg. With respect to specific Aroclors, elevated PCB concentrations were reported for Aroclors 1248, 1254 and 1260, as set forth in Table 1-1, Appendix B.

Pursuant to 40 CFR 761.3, *Excluded PCB Products* includes legally manufactured products with PCB concentrations less than 50 mg/kg. By definition, caulking with PCB concentrations of 50 mg/kg or greater are not *Excluded PCB Products* pursuant to 40 CFR 761.20(a)(1). Therefore, caulking with PCB concentrations equal to or greater than 50 mg/kg will be removed and disposed of off-Site. PCBs concentrations were reported between non-detect (less than one mg/kg) to 3,750 mg/kg, as set forth in Table 1-1, Appendix B and summarized below.

- Total PCB concentrations in samples collected from black caulking at the Site had total PCB concentrations less than 50 mg/kg. Therefore, pursuant to 40 CFR 761.20(a)(1), removal of the black caulking is not required.
- Total PCB concentrations exceeding 50 mg/kg were reported in five out of the seven white caulking samples. Pursuant to 40 CFR 761.20(a)(1), the white caulking with total PCBs greater than 50 mg/kg will be removed and disposed of off-Site at a permitted facility.
- Total PCB concentrations greater than 50 mg/kg were reported in 10 of the 13 samples of grey caulking submitted for laboratory analysis. Pursuant to 40 CFR 761. 20(a)(1), the grey caulking with total PCBs greater than 50 mg/kg will be removed and disposed of off-Site at a permitted facility.

Based upon a visual inspection, the caulking (both grey and white) PCB concentrations less than 50 mg/kg did not appear distinguishable from the caulking with PCB concentrations





greater than 50 mg/kg. Therefore, for the purpose of this Risk-Based Approach, all white and gray window caulking in the building will be assumed to have a total PCB concentration greater than 50 mg/kg, unless otherwise documented.

1.2 SUMMARY OF PROPOSED ABATEMENT ACTIVITIES

With respect to abatement of the PCB-containing caulk, the windows and associated metal framing will be removed by hand using a combination of interior and exterior methods. The exterior work will be conducted using boom lifts. A heavy layer of tack paper will be placed on the interior and exterior sides of the window. The glass will then be broken and will be transported off-Site for disposal as construction and demolition ("C&D") debris. The framing, caulk and remaining glass located within the window frame will be loaded into a 40 cubic yard closed lined, lockable container (the "waste container") stored on-Site pending off-Site transport and disposal.

Caulking will be removed from the adjacent concrete and around the concrete mullions and sills to a single layer surface and the concrete will then sealed with SQIL216 Optically Clear 2-Part Encapsulation material. Upon completion of the concrete encapsulation, wipe samples will be collected from approximately 50% of the sealed concrete areas and the samples will be submitted to a Commonwealth of Massachusetts certified analytical laboratory for PCBs analysis (Method 3540C/8082). Upon receipt of favorable analytical results, the new window frames will then be installed over the sealed concrete to provide additional protection.

Select caulking samples were also submitted for asbestos analysis and, based upon the laboratory analytical results, select samples had elevated levels of asbestos. As a result, removal activities will also be conducted consistent with Commonwealth of Massachusetts Department of Occupational Safety ("MassDOS") regulations (453 CMR 6.00).





2.0 BUILDING MATERIALS CHARACTERIZATION

Characterization of caulking was generally conducted throughout the building and sampling locations were based upon visual consistency of the caulking materials. If necessary, additional sampling may be conducted to confirm that conditions in un-sampled areas are consistent with existing data. Based upon existing data and assumptions set forth in this Risk-Based Approach, Lightship Engineering does not anticipate significant differences in the nature of the caulking present throughout the building.

2.1 CHARACTERIZATION SAMPLE COLLECTION

A summary of the sample collection and laboratory analysis is set forth below.

2.1.1 Sample Collection Methods

On January 11 and 12, 2012, Lightship Engineering collected samples of representative caulking on the exterior portions of the building using a mechanical lift. Prior to sample collection, Lightship Engineering conducted a visual inspection of caulking at each window on each of the five floors of the building to assess the nature and similarity of the caulking. Based upon information provided by Intercontinental, the windows are original to the building, which was constructed in the 1960s.

Exterior Caulking Sampling

The caulking on the exterior portions of the building consisted of primarily white and grey caulking, with some black caulking at select locations. The caulking generally appeared in good condition and appeared to be non-friable. Based upon the visual inspection, the caulking on the exterior portion of the windows appeared consistent throughout the building. Therefore, Lightship Engineering collected a representative sample of approximately five grams of caulking from the windows on each floor and on each of the four sides of the building. Lightship Engineering also collected samples of visually similar caulking along door frames at the front and rear entrances to the building. The samples were placed into laboratory provided sample jars and submitted to a Commonwealth of Massachusetts certified analytical laboratory for PCBs (Method 8082, Extraction Method 3540C) analysis. The laboratory analytical results are summarized in Table 1-1, Appendix B and in Section 2.1.2 below. The laboratory analytical data package is provided at Appendix C.

Interior Caulking Sampling

On the interior of the building, the long, vertical windows on floors two through four were primarily sealed with a grey caulking. The windows on the 5th floor were sealed with white caulking that appeared similar to the white caulking observed on the exterior of the building. Some grey caulking was noted along the frames of the sliding glass doors leading to the 5th floor





balcony. Based upon a visual inspection, the caulking on the interior portion of the windows appeared consistent. Therefore, Lightship Engineering collected a representative sample of approximately five grams of caulking from the windows on floors two through four where grey caulking was observed. Samples were also collected from white window caulking observed on the 5th floor and samples were also collected from the caulking observed along the sliding glass door. The samples were collected in the manner set forth above and were submitted to a Commonwealth of Massachusetts certified analytical laboratory for PCBs (Method 8082, Extraction Method 3540C) analysis. The laboratory analytical results are summarized in Table 1-1, Appendix B and in Section 2.1.2 below. The laboratory analytical data package is provided at Appendix C.

2.1.2 Laboratory Analytical Results

As set forth in Table 1-1, Appendix B, total PCB concentrations ranged between non-detect and 3,750 milligrams per kilogram ("mg/kg"). The range of PCBs detected in the various types of caulk is summarized below.

Caulking Material	Minimum Concentration (mg/kg)	Maximum Concentration (mg/kg)
White	Non-Detect (<1)	919
Grey	3	3,750
Black	3	12

Examples of the caulking materials are provided in Figure 2-1 and 2-2, Appendix A. The laboratory analytical data package is provided as Appendix C.

2.2 DATA USEABILITY ASSESSMENT

As set forth above, all grey and white caulking is conservatively assumed, for the purpose of this SIP, to have PCB concentrations greater than 50 mg/kg. Therefore, the usability of the analytical data for the grey and white caulking is considered appropriate for the intended use.

With respect to the black caulking, concentrations were all well below the 50 mg/kg threshold and, with the exception of the recovery of one surrogate in one sample, the surrogate recoveries were all within the acceptable range. Therefore, the usability of the analytical data for the black caulking is considered appropriate for the intended use.





3.0 PCB CAULKING ABATEMENT ACTIVITIES

The proposed abatement activities are set forth below.

3.1 ABATEMENT PLAN

Renovations at the Site will be conducted floor by floor and are anticipated to begin with the fifth floor. As set forth above, the windows and associated metal framing will be removed by hand using a combination of interior and exterior methods. The exterior work will be conducted using boom lifts. The boom lifts will be prepped with two layers of 6-mil, fire rated polyethylene sheets. The double-layer sheeting will be installed with an extension polyethylene sheeting at the base of the boom platform. The bib extension will be taped to the building during the removal of caulking to prevent caulking from falling to the ground.

Once the boom lift is in place, a heavy layer of tack paper will be placed on the interior and exterior sides of the window. The glass will then be broken and will be transported off-Site for disposal as construction and demolition debris. The framing, caulk and remaining glass will be loaded into a 40 cubic yard closed lined, lockable container (the "waste container") and temporarily stored on-Site. The PCB waste will be transported off-Site for disposal as set forth in Section 3.3.

The building owner may select to re-use the metal window frames on the fifth and first floors. In the event the framing is reused, the removal procedures will be consistent with the method set forth above. Once the framing has been removed, remaining glass and caulking will be removed from the frame using blade scrapers and placed in labeled 55-gallon drums or in the waste container. Each metal frame will be double washed and/or rinsed, consistent with the USEPA's Wipe Sampling and Double Wash/Rinse Cleanup method dated April 18, 1991. One wipe sample will be collected from each of the cleaned window frames consistent with 40 CFR 761.123 and will be submitted to a Commonwealth of Massachusetts certified analytical laboratory for PCBs analysis (Method 3540C/8082). Assuming PCB concentrations are below 1 microgram per 100 square centimeters ("ug/100cm²"), the window framing will be re-used at the Site. The frames will be cleaned until favorable wipe samples are obtained or the frames will be disposed as PCB, as set forth in Section 3.3.

Caulking will be removed from the adjacent concrete and around the concrete mullions and sills to a single layer surface using various cutting tools, including: an electric caulking cutter to reach deeper caulking; a 5-in-1 tool designed to dig-in and remove recessed caulking; and, a razor scraper to remove caulking close to the surface. Upon removal of the caulking, concrete will then sealed with SQIL216 Optically Clear 2-Part Encapsulation silicone coating (the "concrete sealant"). A copy of the concrete sealant Technical Data Sheet is provided as Appendix D. Prior to the application of the concrete sealant and after the removal of the windows and caulk from the concrete, Lightship Engineering will collect concrete samples from approximately 10% of the window openings (estimated to be 725 windows, therefore





3.5 SITE RESTORATION

The removed windows will be replaced with new windows and, as set forth above, sealed concrete will be covered with the concrete sealant and new window frames.

3.6 RECORDKEEPING AND DOCUMENTATION

The following recordkeeping and documentation activities will be conducted in connection with the abatement activities.

3.6.1 Field Notes

A daily log of on-Site activities will be maintained and will include:

- Summary of daily health and safety meetings;
- Field procedures and observations;
- Removal, abatement, containment, and decontamination progress;
- Sample locations with selection criteria, samples collected, analyses performed, sample handling;
- Health and safety monitoring activities and data;
- Estimate of wastes generated and stored; and
- Waste transportation summaries, if applicable.

3.6.2 Photographs


A daily photograph log will be generated of activities such as removal and abatement work, containment structures, decontamination, sampling, and waste handling and storage.

3.6.3 Transport and Disposal Documentation

Manifests and/or bills of lading for the transportation, treatment, and disposal of regulated waste materials and certifications of the treatment of the wastes, if necessary, will be obtained from the transporter and from the treatment and/or disposal facility. Copies of these forms will be included in the abatement report, and records will be maintained consistent with 40 CFR 761 Subpart K (PCB Waste Disposal Records and Reports).

3.6.4 Abatement Completion Report

An abatement report will be prepared upon completion of remedial activities that will include the following information:





White Caulking 5th Floor Window



Grey Caulking on Top of Concrete Structure



Grey Caulking on Interior 5th Floor



Grey Caulking as Base of Concrete Structure



Grey and White Caulking on Sliding Door Frame 5th Floor



Grey Caulking on Exterior

Grey Caulking on Interior Window



Grey Caulking on Interior 2nd Floor



Grey Caulking on Interior 2nd Floor



White Caulking 5th Floor Window

Client	
Intercontinental Management Corp.	
1270 Soldiers Field Road	
Boston, Massachusetts 02135	

Source:

Commercial Property 130 Bishop Allen Drive Cambridge, Massachusetts 02139

Project

FIGURE 2-2 Examples of Caulking in Contact with Building Materials



Date: 1/23/2012	Drawn by: TC	522.72.1
Sheet No. 1 of 1	Scale: N.T.S.	532.72.1

Projects/532 - Intercontinental/532.72 - Bishop Allen, Cambridge/Letter Report/Figures.dwg

PCB Concentrations in Caulking Table 1-1 (mg/kg)

			_	J.	บอร์	Col	CB	d	-	8	
	Sample ID.	Aroclor 1016	Aroclor 1221	Aroclor 1232	Aroclor 1242	Aroclor 1248	Aroclor 1254	Aroclor 1260	Aroclor 1262	Aroclor 1268	Total PCBs
	Black LECSE-1.31	0.58 U	0.58 U	0.58 U	0.58 U	4.28	2.06	9.0	U 61.0	0.19 U	7
	Black LECSE-5.57	0.6 U	0.6 U	0.6 U	O 9.0	7.26	3.34	1.65	0.2 U	0.2 U	12
	ECSS-1.7	0.21	0.21	0.21	0.21 U	0.14 U	4.26	3.2	0.07	0.07 U	7
	Elack FECSS-5.4	0.57 U	0.57 U	J 0.57 U	0.57 U	4.33	2.28	1.89	0.19	J 61.0	6
	ECSW-5.37	0.41	0.41 U	0.41 U	0.41	5.08	5.07	2.32	0.14 U	0.14 U	12
	Black (Brick)	1.07	1 201	1.07 U	1.07	7.8	2.28	98.0	0.36	0.36 U	Ξ
0 0	Black LECSN-5.2	0.12	0.12 1.	0.12 U	0.12	0.78	68.0	6.0	0.04	0.04 U	m
	Crey/Black (Door)	1.31	1.31	1.31	1.31	6.87	10.7	0.87	0.44	0.44	81
	LECSS(1)-5.18 White (Interior)	1 8.11	11.8	11.8 U	11.8 U	7.87 U	11.8	7.87	3.94 U	3.94	QN
	LECSN-3.2	0.29	0.29 U	U 670	0.29 U	U 61.0	0.29 U	O 61.0	U 1.0	I 0.1 U	QN
	PECSE-4.17	5.47 U	5.47 U	5.47 U	5.47 U	92.4	5.47 U	3.65 U	1.82 U	1.82 U	92
	LECSW-1.37 White (Door)	248 U	248 U	248 U	248 U	616	248 U	165 U	82.6 U	82.6 U	616
	LECSW-3.22	1 68'L	7.89	0.687	O 68'L	6.86	7.89 U	5.26 U	2.63 U	2.63 U	66
	White LECSS-4.3	3.6	N 9.8	0.8	N 9'8	89	8.6 U	5.73 U	2.87 U	2.87 U	89
	LECSE(I)-4.40 White (Interior)	3.9	3.0	6.€	17.1	11.9	24	2.6	1.3	1.3	53

			Į,	ouoi	Cog	CB	d			Г
Sample ID.	Aroclor 1016	Aroclor 1221	Aroclor 1232	Aroclor 1242	Aroclor 1248	Aroclor 1254	Aroclor 1260	Aroclor 1262	Aroclor 1268	Total PCBs
Grey CECSE-2.86	29.1 U	29.1 U	29.1 U	29.1 U	569	29.1 U	35.4	9.71 U	0.71 U	304
Grey Grey	29.7 U	29.7 U	29.7 U	29.7 U	647	29.7 U	54.9	N 6'6	D 6'6	702
Guey LECSS-2.10	26.5 U	26.5 U	26.5 U	26.5 U	396	26.5 U	48.7	8.85 U	8.85 U	445
Grey CECSS-3.12	23.6 U	23.6 U	23.6 U	23.6 U	380	23.6 U	48.2	7.87	7.87	428
Grey LECSW-2.12	26.5 U	26.5 U	26.5 U	26.5 U	288	26.5 U	42.1	8.85	8.85	330
Gtey LECSW-4.90	0.23 L	0,23 t	0.23	0.23	0.15 t	1.68	1.36	0.07	0.07	3
Grey LECSN-2.14	1 30 1	30 1	30 1	30 1	253	30 1	38.5	1 01 (10 1	292
Grey LECSN-4,12	9 0.3	0.3	0.3	0.3	0.63	0.58	0.4	1.0.1	1.0	2
LECSW-5.66.1	U 0.23 U	U 0.23 U	U 0.23 U	U 0.23 U	5.03	4.8	0.15 U	0.08 (U 0.08 U	10
Gtey (Door) LECSW-5.66.2	J 291 U	1 291 11	7 291 U	J 167	1270	2480	194 U	O 1726	0 1.79 U	3,750
LECSS(I)-4.24 Grey (Interior)	28.8 U	28.8 U	28.8 U	28.8 U	19.2 U	88.3	19.2 U	9.62 U	9.62 U	108
LECSW(I)-4.74 Grey (Interior)	5.77 U	5.77 U	5.77 U	5.77 U	73	47.8	3.85 U	1.92	1.92	121
LECSN(I)-4,4 Grey (Interior)	5.13	50.00	5.13	5.13	30.1	27.4	3.42	1.71	1.71	58

0.11 U - Concentration reported below analytical reporting limite of 0.41 mg/kg.
7.8 - Reported concentration of PCB cogener (mg/kg).
253 - Reported concentration of specific PCB cogener exceeds USEPA action threshold of 50 mg/kg.
53 - Total PCB concentration exceeds USEPA action threshold of 50 mg/kg.
54 - Total PCB concentration exceeds USEPA action threshold of 500 mg/kg.
ND - PCBs reported at non-detectable levels.



ANALYTICAL REPORT

Lab Number: L1200581

Client: Lightship Engineering

39 Industrial Park Road

Unit C

Plymouth, MA 02360

ATTN: Tim Condon

Phone: (508) 830-3344

Project Name: 130 BISHOP ALLEN DRIVE

Project Number: 532.72.1

Report Date: 01/19/12

The original project report/data package is held by Alpha Analytical. This report/data package is paginated and should be reproduced only in its entirety. Alpha Analytical holds no responsibility for results and/or data that are not consistent with the original.

Certifications & Approvals: MA (M-MA086), NY (11148), CT (PH-0574), NH (2003), NJ NELAP (MA935), RI (LAO00065), ME (MA00086), PA (68-03671), USDA (Permit #P-330-11-00240), NC (666), TX (T104704476), DOD (L2217), US Army Corps of Engineers.

Eight Walkup Drive, Westborough, MA 01581-1019 508-898-9220 (Fax) 508-898-9193 800-624-9220 - www.alphalab.com



Project Name: 130 BISHOP ALLEN DRIVE

Lab Number:

L1200581

Project Number: 532.72.1

Report Date:

01/19/12

MADEP MCP Response Action Analytical Report Certification

This form provides certifications for all samples performed by MCP methods. Please refer to the Sample Results and Container Information sections of this report for specification of MCP methods used for each analysis. The following questions pertain only to MCP Analytical Methods.

Α	Were all samples received in a condition consistent with those described on the Chain-of- Custody, properly preserved (including temperature) in the field or laboratory, and prepared/analyzed within method holding times?	YES
В	Were the analytical method(s) and all associated QC requirements specified in the selected CAM protocol(s) followed?	YES
С	Were all required corrective actions and analytical response actions specified in the selected CAM protocol(s) implemented for all identified performance standard non-conformances?	YES
D	Does the laboratory report comply with all the reporting requirements specified in CAM VII A, "Quality Assurance and Quality Control Guidelines for the Acquisition and Reporting of Analytical Data?"	YES
E a.	VPH, EPH, and APH Methods only: Was each method conducted without significant modification(s)? (Refer to the individual method(s) for a list of significant modifications).	N/A
Eb.	APH and TO-15 Methods only: Was the complete analyte list reported for each method?	N/A
F	Were all applicable CAM protocol QC and performance standard non-conformances identified and evaluated in a laboratory narrative (including all "No" responses to Questions A through E)?	YES

G 	Were the reporting limits at or below all CAM reporting limits specified in the selected CAM protocol(s)?	NO
Н	Were all QC performance standards specified in the CAM protocol(s) achieved?	NO
l	Were results reported for the complete analyte list specified in the selected CAM protocol(s)?	

For any questions answered "No", please refer to the case narrative section on the following page(s).

Please note that sample matrix information is located in the Sample Results section of this report.



Project Number: 130 BISHOP ALLEN DRIVE Lab Number: L1200581

Project Number: 532 72 1

Perport Date: 04/49/42

Project Number: 532.72.1 Report Date: 01/19/12

Case Narrative (continued)

analysis.

L1200581-21 has elevated detection limits due to the dilution required by the matrix interferences encountered during the concentration of the sample and the analytical dilution required by the sample matrix.

In reference to question G:

One or more of the target analytes did not achieve the requested CAM reporting limits.

In reference to question H:

The surrogate recovery for L1200581-01 is outside the individual acceptance criteria for Decachlorobiphenyl (29%), but within the overall method allowances. The results of the original analysis are reported; however, all associated compounds are considered to have a potential bias.

The surrogate recoveries for L1200581-02, -03, -04, -07, -08, -09, -11, -12, -13, -16, -17, -21, and -23 through -28 are below the acceptance criteria for 2,4,5,6-Tetrachloro-m-xylene and Decachlorobiphenyl (all 0%) due to the dilutions required to quantitate the samples. Re-extraction was not required; therefore, the results of the original analyses are reported.

L1200581-18: The internal standard (IS) response for 1-Bromo-2-nitrobenzene was above the acceptance criteria on the confirmation column; however, the sample was not re-analyzed due to obvious interferences. Since the IS response was above method criteria, all associated compounds are considered to have a potentially low bias. Due to the high IS response, the surrogate recoveries for 2,4,5,6-Tetrachloro-m-xylene (10%) and Decachlorobiphenyl (4%) are below the individual acceptance criteria on the confirmation column. The surrogate recoveries for L1200581-19 were below the acceptance criteria for 2,4,5,6-Tetrachloro-m-xylene (9%/9%) and Decachlorobiphenyl (3%/4%); however, re-extraction achieved similar results: 2,4,5,6-Tetrachloro-m-xylene (26%/26%) and Decachlorobiphenyl (24%/22%). The results of both extractions are reported; however, all associated compounds are considered to have a potentially low bias.

The dual column RPD for L1200581-19RE is above the acceptance criteria for Aroclor 1254; however, no

obvious column interferences are present. The higher of the two results is reported and qualified with a "P". The surrogate recoveries for L1200581-20 were below the acceptance criteria for 2,4,5,6-Tetrachloro-m-xylene (16%/7%) and Decachlorobiphenyl (5%/7%); however, re-extraction achieved similar results: Decachlorobiphenyl (27%/27%). The results of both extractions are reported; however, all associated compounds are considered to have a potentially low bias.



ORGANICS



01/19/12

Project Name: 130 BISHOP ALLEN DRIVE Lab Number: L1200581

Project Number: 532.72.1

SAMPLE RESULTS

 Lab ID:
 L1200581-01
 D
 Date Collected:
 01/10

 Client ID:
 LECSE-1.31
 Date Received:
 01/1

Sample Location: CAMBRIDGE, MA
Matrix: Solid

Matrix: Solid
Analytical Method: 97,8082
Analytical Date: 01/17/12 15:10

Analyst: SH

Percent Solids: Results reported on an 'AS RECEIVED' basis.

Date Collected: 01/10/12 10:30
Date Received: 01/11/12
Field Prep: Not Specified
Extraction Method: EPA 3540C
Extraction Date: 01/13/12 16:30
Cleanup Method1: EPA 3665A
Cleanup Date1: 01/16/12

Report Date:

Cleanup Method2: EPA 3660B Cleanup Date2: 01/16/12

Parameter	Result	Qualifier	Units	RL	MDL	Dilution Factor
MCP Polychlorinated Biphenyls - W	estborough Lab					
Aroclor 1016	ND		ug/kg	584		5
Aroclor 1221	ND		ug/kg	584		5
Aroclor 1232	ND		ug/kg	584	122	5
Aroclor 1242	ND		ug/kg	584		5
Aroclor 1254	2060		ug/kg	584	1.00	5
Aroclor 1262	ND		ug/kg	194		5
Aroclor 1268	ND		ug/kg	194	122	5

Surrogate	% Recovery	Qualifier	Acceptance Criteria	
2,4,5,6-Tetrachloro-m-xylene	38		30-150	
Decachlorobiphenyl	29	Q	30-150	
2,4,5,6-Tetrachloro-m-xylene	34		30-150	
Decachlorobiphenyl	30		30-150	



Project Name: 130 BISHOP ALLEN DRIVE Lab Number: L1200581

Project Number: 532.72.1 Report Date: 01/19/12

SAMPLE RESULTS

Lab ID: L1200581-02 D
Client ID: LECSE-2.86
Sample Location: CAMBRIDGE, MA
Matrix: Solid

Analytical Method: 97,8082
Analytical Date: 01/17/12 23:16

Analyst: KB

Percent Solids: Results reported on an 'AS RECEIVED' basis.

Date Collected: 01/10/12 09:15 Date Received: 01/11/12 Field Prep: Not Specified Extraction Method: **EPA 3580A** Extraction Date: 01/17/12 18:30 Cleanup Method1: EPA 3665A Cleanup Date1: 01/17/12 Cleanup Method2: **EPA 3660B**

Cleanup Method2: EPA 3660 Cleanup Date2: 01/17/12

Parameter	Result	Qualifier	Units	RL	MDL	Dilution Factor
MCP Polychlorinated Biphenyls	- Westborough Lab					
Aroclor 1016	ND		ug/kg	29100	-	10
Aroclor 1221	ND		ug/kg	29100	-	10
Aroclor 1232	ND		ug/kg	29100		10
Aroclor 1242	ND		ug/kg	29100		10
Aroclor 1254	ND		ug/kg	29100		10
Aroclor 1262	ND		ug/kg	9710		10
Aroclor 1268	ND		ug/kg	9710	-	10

Surrogate	% Recovery	Qualifier	Acceptance Criteria	
2,4,5,6-Tetrachloro-m-xylene	0	Q	30-150	
Decachlorobiphenyl	0	Q	30-150	
2,4,5,6-Tetrachloro-m-xylene	0	Q	30-150	
Decachlorobiphenyl	0	Q	30-150	



01/19/12

Project Name: 130 BISHOP ALLEN DRIVE Lab Number: L1200581 Report Date:

Project Number: 532.72.1

SAMPLE RESULTS

Lab ID: D L1200581-03 Client ID: LECSE-3.2 Sample Location: CAMBRIDGE, MA

Matrix: Solid 97,8082 Analytical Method: 01/17/12 23:30 Analytical Date:

Analyst: KB

Percent Solids: Results reported on an 'AS RECEIVED' basis. Date Collected: 01/10/12 08:30 Date Received: 01/11/12 Field Prep: Not Specified Extraction Method: **EPA 3580A** Extraction Date: 01/17/12 18:30 Cleanup Method1: EPA 3665A

Cleanup Date1: 01/17/12 Cleanup Method2: EPA 3660B Cleanup Date2: 01/17/12

Parameter	Result	Qualifier	Units	RL	MDL	Dilution Factor
MCP Polychlorinated Biphenyls	s - Westborough Lab					
Aroclor 1016	ND		ug/kg	29700		10
Aroclor 1221	ND		ug/kg	29700		10
Aroclor 1232	ND		ug/kg	29700		10
Aroclor 1242	ND		ug/kg	29700		10
Aroclor 1254	ND		ug/kg	29700		10
Aroclor 1260	54900		ug/kg	19800		10
Aroclor 1262	ND		ug/kg	9900		10
Aroclor 1268	ND		ug/kg	9900		10

Surrogate	% Recovery	Qualifier	Acceptance Criteria
2,4,5,6-Tetrachloro-m-xylene	0	Q	30-150
Decachlorobiphenyl	0	Q	30-150
2,4,5,6-Tetrachloro-m-xylene	0	Q	30-150
Decachlorobiphenyl	0	Q	30-150



Project Name: 130 BISHOP ALLEN DRIVE Lab Number: L1200581

Project Number: 532.72.1 Report Date: 01/19/12

SAMPLE RESULTS

Lab ID: L1200581-04 D

Client ID: LECSE-4.17

Sample Location: CAMBRIDGE, MA

Matrix: Solid

Matrix: Solid
Analytical Method: 97,8082
Analytical Date: 01/18/12 13:21

Analyst: SH

Percent Solids: Results reported on an 'AS RECEIVED' basis.

01/10/12 08:45 Date Collected: Date Received: 01/11/12 Field Prep: Not Specified Extraction Method: **EPA 3540C** Extraction Date: 01/13/12 16:30 Cleanup Method1: EPA 3665A 01/16/12 Cleanup Date1: Cleanup Method2: EPA 3660B

Cleanup Date2: 01/16/12

Parameter	Result	Qualifier	Units	RL	MDL	Dilution Factor
MCP Polychlorinated Biphenyls	- Westborough Lab					
Aroclor 1016	ND		ug/kg	5470		50
Aroclor 1221	ND		ug/kg	5470		50
Aroclor 1232	ND		ug/kg	5470		50
Aroclor 1242	ND		ug/kg	5470	221	50
Aroclor 1254	ND		ug/kg	5470		50
Aroclor 1260	ND		ug/kg	3650	52 4	50
Aroclor 1262	ND		ug/kg	1820		50
Aroclor 1268	ND		ug/kg	1820		50

% Recovery	Qualifier	Acceptance Criteria	
0	Q	30-150	
	0 0	0 Q 0 Q 0 Q	% Recovery Qualifier Criteria 0 Q 30-150 0 Q 30-150 0 Q 30-150



Project Name: 130 BISHOP ALLEN DRIVE Lab Number: L1200581

Project Number: 532.72.1 Report Date: 01/19/12

SAMPLE RESULTS

 Lab ID:
 L1200581-05
 D
 Date Collection:

 Client ID:
 LECSE-5.57
 Date Recentage Properties of the properti

Analytical Date: 01/17/12 13:30
Analyst: SH

Percent Solids: Results reported on an 'AS RECEIVED' basis.

Date Collected: 01/10/12 10:00 Date Received: 01/11/12 Field Prep: Not Specified Extraction Method: **EPA 3540C** Extraction Date: 01/13/12 16:30 Cleanup Method1: EPA 3665A Cleanup Date1: 01/16/12 Cleanup Method2: EPA 3660B Cleanup Date2: 01/16/12

Parameter	Result	Qualifier	Units	RL	MDL	Dilution Factor
MCP Polychlorinated Biphenyls	- Westborough Lab			N. Person		
Aroclor 1016	ND		ug/kg	595		5
Aroclor 1221	ND		ug/kg	595	-	5
Aroclor 1232	ND		ug/kg	595	/227	5
Aroclor 1242	ND		ug/kg	595		5
Aroclor 1248	7260		ug/kg	397		5
Aroclor 1254	3340		ug/kg	595		5
Aroclor 1262	ND		ug/kg	198		5
Aroclor 1268	ND		ug/kg	198	0.00	5

	Acceptance						
Surrogate	% Recovery	Qualifier	Criteria				
2,4,5,6-Tetrachloro-m-xylene	92		30-150				
Decachlorobiphenyl	72		30-150				
2,4,5,6-Tetrachloro-m-xylene	73		30-150				
Decachlorobiphenyl	70		30-150				



01/10/12 15:30

Not Specified

01/11/12

Project Name: 130 BISHOP ALLEN DRIVE Lab Number: L1200581

Project Number: 532.72.1 Report Date: 01/19/12

SAMPLE RESULTS

Lab ID: L1200581-06 Date Collected:
Client ID: LECSS-1.7 Date Received:
Sample Location: CAMBRIDGE, MA Field Prep:
Matrix: Solid Extraction Method:

Matrix:SolidExtraction Method:EPA 3540CAnalytical Method:97,8082Extraction Date:01/13/12 16:30Analytical Date:01/16/12 14:20Cleanup Method1:EPA 3665AAnalyst:SHCleanup Date1:01/16/12

Analyst: SH Cleanup Date1: 01/16/12
Percent Solids: Results reported on an 'AS RECEIVED' basis. Cleanup Method2: EPA 3660B

Cleanup Date2: 01/16/12

Parameter	Result	Qualifier	Units	RL	MDL	Dilution Factor
MCP Polychlorinated Biphenyls	- Westborough Lab					
Aroclor 1016	ND		ug/kg	211	8	2
Aroclor 1221	ND		ug/kg	211		2
Aroclor 1232	ND		ug/kg	211		2
Aroclor 1242	ND		ug/kg	211	1221	2
Aroclor 1248	ND		ug/kg	141		2
Aroclor 1260	3200		ug/kg	141	-	2
Aroclor 1262	ND		ug/kg	70.4	-	2
Aroclor 1268	ND		ug/kg	70.4		2

			Acceptance	
Surrogate	% Recovery	Qualifier	Criteria	
2,4,5,6-Tetrachloro-m-xylene	75		30-150	
Decachlorobiphenyl	69		30-150	
2,4,5,6-Tetrachloro-m-xylene	74		30-150	
Decachlorobiphenyl	81		30-150	



Project Name: 130 BISHOP ALLEN DRIVE Lab Number: L1200581

Project Number: 532.72.1 Report Date: 01/19/12

SAMPLE RESULTS

Lab ID: L1200581-07 D

Client ID: LECSS-2.10

Sample Location: CAMBRIDGE, MA

Matrix: Solid

Matrix: Solid
Analytical Method: 97,8082
Analytical Date: 01/17/12 23:44

Analyst: KB

Percent Solids: Results reported on an 'AS RECEIVED' basis.

Date Collected: 01/10/12 12:00
Date Received: 01/11/12
Field Prep: Not Specified
Extraction Method: EPA 3580A
Extraction Date: 01/17/12 18:30
Cleanup Method1: EPA 3665A
Cleanup Date1: 01/17/12

Cleanup Method2: EPA 3660B Cleanup Date2: 01/17/12

Parameter	Result	Qualifier	Units	RL	MDL	Dilution Factor
MCP Polychlorinated Biphenyls -	Westborough Lab				belga	
Aroclor 1016	ND		ug/kg	26500		10
Aroclor 1221	ND		ug/kg	26500	500	10
Aroclor 1232	ND		ug/kg	26500		10
Aroclor 1242	ND		ug/kg	26500		10
Aroclor 1254	ND		ug/kg	26500		10
Aroclor 1262	ND		ug/kg	8850		10
Aroclor 1268	ND		ug/kg	8850		10

		Acceptance	
% Recovery	Qualifier	Criteria	
0	Q	30-150	
	0 0 0	0 Q 0 Q 0 Q	% Recovery Qualifier Criteria 0 Q 30-150 0 Q 30-150 0 Q 30-150



Project Name: 130 BISHOP ALLEN DRIVE Lab Number: L1200581

Project Number: 532.72.1 Report Date: 01/19/12

SAMPLE RESULTS

Lab ID: L1200581-08 D Date Collected:
Client ID: LECSS-3.12 Date Received:
Sample Location: CAMBRIDGE, MA
Matrix: Solid Extraction Methor

Analytical Method: 97,8082
Analytical Date: 01/17/12 23:59
Analyst: KB

Percent Solids: Results reported on an 'AS RECEIVED' basis.

01/10/12 11:30 Date Received: 01/11/12 Field Prep: Not Specified Extraction Method: EPA 3580A Extraction Date: 01/17/12 18:30 EPA 3665A Cleanup Method1: Cleanup Date1: 01/17/12 Cleanup Method2: **EPA 3660B** Cleanup Date2: 01/17/12

Parameter	Result	Qualifier	Units	RL	MDL	Dilution Factor
MCP Polychlorinated Biphenyl	s - Westborough Lab		L'épunt par			
Aroclor 1016	ND		ug/kg	23600		10
Aroclor 1221	ND		ug/kg	23600	844	10
Aroclor 1232	ND		ug/kg	23600		10
Aroclor 1242	ND		ug/kg	23600	-	10
Aroclor 1254	ND		ug/kg	23600	-	10
Aroclor 1262	ND		ug/kg	7870		10
Aroclor 1268	ND		ug/kg	7870		10

Surrogate	% Recovery	Qualifier	Acceptance Criteria
2,4,5,6-Tetrachloro-m-xylene	0	Q	30-150
Decachlorobiphenyl	0	Q	30-150
2,4,5,6-Tetrachloro-m-xylene	0	Q	30-150
Decachlorobiphenyl	0	Q	30-150



Lab Number:

L1200581

Report Date: 01/19/12

Project Number: 532.72.1

SAMPLE RESULTS

Lab ID:

L1200581-09

Client ID:

LECSS-4.3

Sample Location: Matrix:

Project Name:

CAMBRIDGE, MA

130 BISHOP ALLEN DRIVE

Analytical Method:

Solid 97,8082

Analytical Date:

01/18/12 17:02

Analyst:

SH

Percent Solids:

Results reported on an 'AS RECEIVED' basis.

D

Date Collected: Date Received: 01/10/12 11:00

Field Prep:

01/11/12 Not Specified **EPA 3540C**

Extraction Method: Extraction Date:

01/13/12 16:30

Cleanup Method1: Cleanup Date1:

EPA 3665A 01/17/12

Cleanup Method2:

EPA 3660B

01/17/12 Cleanup Date2:

Parameter	Result	Qualifier	Units	RL	MDL	Dilution Factor
MCP Polychlorinated Bipheny	s - Westborough Lab					
Aroclor 1016	ND		ug/kg	8600		80
Aroclor 1221	ND		ug/kg	8600	-	80
Aroclor 1232	ND		ug/kg	8600		80
Aroclor 1242	ND		ug/kg	8600		80
Aroclor 1254	ND		ug/kg	8600		80
Aroclor 1260	ND		ug/kg	5730		80
Aroclor 1262	ND		ug/kg	2870		80
Aroclor 1268	ND		ug/kg	2870	22	80
			Accentan	••		

		Acceptance	
% Recovery	Qualifier	Criteria	
0	Q	30-150	
	0 0 0	0 Q 0 Q 0 Q	% Recovery Qualifier Criteria 0 Q 30-150 0 Q 30-150 0 Q 30-150

Lab Number: 130 BISHOP ALLEN DRIVE

Project Name: L1200581 **Project Number:** Report Date: 532.72.1 01/19/12

SAMPLE RESULTS

Lab ID: L1200581-10 D LECSS-5.4 Client ID: CAMBRIDGE, MA Sample Location: Matrix: Solid

Decachlorobiphenyl

Analytical Method: 97,8082 01/17/12 13:42 Analytical Date:

Analyst: SH

Results reported on an 'AS RECEIVED' basis. Percent Solids:

01/10/12 10:30 Date Collected: Date Received: 01/11/12 Field Prep: Not Specified Extraction Method: EPA 3540C Extraction Date: 01/13/12 16:30 **EPA 3665A** Cleanup Method1: Cleanup Date1: 01/16/12

Cleanup Method2: **EPA 3660B** Cleanup Date2: 01/16/12

Parameter		Result	Qualifier	Units	RL	MDL	Dilution Factor
MCP Polyc	hlorinated Biphenyls - Westbor	ough Lab					
Aroclor 1016		ND		ug/kg	568		5
Aroclor 1221		ND		ug/kg	568		5
Aroclor 1232		ND		ug/kg	568		5
Aroclor 1242		ND		ug/kg	568	-	5
Aroclor 1248		4330		ug/kg	379		5
Aroclor 1254		2280		ug/kg	568	344	5
Aroclor 1260		1890		ug/kg	379		5
Aroclor 1262		ND		ug/kg	189		5
Aroclor 1268		ND		ug/kg	189	- <u></u>	5
	Surrogate	% Recovery	Qualifier	Acceptance Criteria			
	2,4,5,6-Tetrachloro-m-xylene	50		30-150			
	Decachlorobiphenyl	35		30-150			
	2,4,5,6-Tetrachloro-m-xylene	40		30-150			

38

30-150

Lab Number: L1200581

130 BISHOP ALLEN DRIVE 532.72.1

Report Date:

Project Number:

01/19/12

SAMPLE RESULTS

Lab ID: Client ID: L1200581-12 LECSW-2.12

01/10/12 13:30 Date Collected:

Sample Location:

Project Name:

CAMBRIDGE, MA

Date Received: 01/11/12

Matrix: Solid Analytical Method:

Field Prep:

Not Specified **EPA 3580A**

97,8082 01/18/12 00:41 Analytical Date:

Extraction Method: **Extraction Date:**

01/17/12 18:30

KB Analyst:

Cleanup Method1: Cleanup Date1:

EPA 3665A 01/17/12

Percent Solids:

Cleanup Method2:

EPA 3660B

Results reported on an 'AS RECEIVED' basis.

D

01/17/12 Cleanup Date2:

Parameter	Result	Qualifier	Units	RL	MDL	Dilution Factor
MCP Polychlorinated Biphenyls	- Westborough Lab					
Aroclor 1016	ND		ug/kg	26500	(<u>-</u>	10
Aroclor 1221	ND		ug/kg	26500		10
Aroclor 1232	ND		ug/kg	26500	977	10
Aroclor 1242	ND		ug/kg	26500		10
Aroclor 1254	ND		ug/kg	26500		10
Aroclor 1262	ND		ug/kg	8850		10
Aroclor 1268	ND		ug/kg	8850	7.	10

			Acceptance	
Surrogate	% Recovery	Qualifier	Criteria	0.00
2,4,5,6-Tetrachloro-m-xylene	0	Q	30-150	
Decachlorobiphenyl	0	Q	30-150	
2,4,5,6-Tetrachloro-m-xylene	0	Q	30-150	
Decachlorobiphenyl	0	Q	30-150	



Lab Number: L1200581

Project Number: 532.72.1 Report Date: 01/19/12

SAMPLE RESULTS

130 BISHOP ALLEN DRIVE

Project Name:

WI EL KLOOLIO

Lab ID:L1200581-13DDate Collected:01/10/12 12:30Client ID:LECSW-3.22Date Received:01/11/12Sample Location:CAMBRIDGE, MAField Prep:Not Specified

Field Prep: Not Specified CAMBRIDGE, MA Sample Location: Extraction Method: **EPA 3540C** Solid Matrix: Extraction Date: 01/17/12 13:00 Analytical Method: 97,8082 **EPA 3665A** Cleanup Method1: Analytical Date: 01/18/12 14:57 Cleanup Date1: 01/18/12

Analyst: SH Cleanup Date1: 01/18/12
Percent Solids: Results reported on an 'AS RECEIVED' basis. Cleanup Method2: EPA 3660B

Cleanup Date2: 01/18/12

Parameter		Result	Qualifier	Units	RL	MDL	Dilution Factor
MCP Polyc	hlorinated Biphenyls - Westbore	ough Lab					
Aroclor 1016		ND		ug/kg	7890	-	20
Aroclor 1221		ND		ug/kg	7890		20
Aroclor 1232		ND		ug/kg	7890		20
Aroclor 1242		ND		ug/kg	7890		20
Aroclor 1248		98900		ug/kg	5260		20
Aroclor 1254		ND		ug/kg	7890		20
Aroclor 1260		ND		ug/kg	5260		20
Aroclor 1262		ND		ug/kg	2630		20
Aroclor 1268		ND		ug/kg	2630		20
	Surrogate	% Recovery	Qualifier	Acceptance Criteria			
	2,4,5,6-Tetrachloro-m-xylene	0	Q	30-150			
	Decachlorobiphenyl	0	Q	30-150			
	2,4,5,6-Tetrachloro-m-xylene	0	Q	30-150			

Q

30-150



Decachlorobiphenyl

Lab Number: L1200581

Report Date: 01/19/12

Project Number: 532.72.1

SAMPLE RESULTS

Lab ID: L1200581-15 Client ID: LECSW-5.37 CAMBRIDGE, MA Sample Location:

Matrix: Solid Analytical Method: 97,8082 01/18/12 09:52 Analytical Date:

SH Analyst:

Project Name:

Percent Solids: Results reported on an 'AS RECEIVED' basis.

130 BISHOP ALLEN DRIVE

01/10/12 12:45 Date Collected: Date Received: 01/11/12 Field Prep: Not Specified Extraction Method: **EPA 3540C** Extraction Date: 01/17/12 13:00 Cleanup Method1: EPA 3665A Cleanup Date1: 01/18/12 Cleanup Method2: **EPA 3660B**

01/18/12 Cleanup Date2:

Parameter	Result	Qualifier	Units	RL	MDL	Dilution Factor
MCP Polychlorinated Biphenyls - V	Vestborough Lab					
Aroclor 1016	ND		ug/kg	411	100	1
Aroclor 1221	ND		ug/kg	411		1
Aroclor 1232	ND		ug/kg	411		1
Aroclor 1242	ND		ug/kg	411		1
Aroclor 1248	5080		ug/kg	274		1
Aroclor 1260	2320		ug/kg	274		1
Aroclor 1262	ND		ug/kg	137	1000	1
Aroclor 1268	ND		ug/kg	137		1

		Acceptance	
% Recovery	Qualifier	Criteria	
91		30-150	
93		30-150	
98		30-150	
94		30-150	
	91 93 98	91 93 98	91 30-150 93 30-150 98 30-150



01/19/12

Project Name: 130 BISHOP ALLEN DRIVE Lab Number: L1200581

Project Number: 532.72.1 Report Date:

SAMPLE RESULTS

Lab ID: L1200581-16 D Date Collected Client ID: LECSN-1.24 Date Received Sample Location: CAMBRIDGE, MA Field Prep:

Matrix: Solid
Analytical Method: 97,8082
Analytical Date: 01/17/12 12:40

Analyst: SH

Percent Solids: Results reported on an 'AS RECEIVED' basis.

Date Collected: 01/10/12 15:25
Date Received: 01/11/12
Field Prep: Not Specified
Extraction Method: EPA 3540C
Extraction Date: 01/13/12 16:30
Cleanup Method1: EPA 3665A
Cleanup Date1: 01/16/12
Cleanup Method2: EPA 3660B

Cleanup Method2: EPA 3660l Cleanup Date2: 01/16/12

Parameter	Result	Qualifier	Units	RL	MDL	Dilution Factor
MCP Polychlorinated Biphenyl	s - Westborough Lab					
Aroclor 1016	ND		ug/kg	1070		10
Aroclor 1221	ND		ug/kg	1070	-2	10
Aroclor 1232	ND		ug/kg	1070		10
Aroclor 1242	ND		ug/kg	1070	-	10
Aroclor 1248	7800		ug/kg	714		10
Aroclor 1254	2280		ug/kg	1070		10
Aroclor 1262	ND		ug/kg	357		10
Aroclor 1268	ND		ug/kg	357	-	10

			Acceptance	
Surrogate	% Recovery	Qualifier	Criteria	
2,4,5,6-Tetrachloro-m-xylene	0	Q	30-150	
Decachlorobiphenyl	0	Q	30-150	
2,4,5,6-Tetrachloro-m-xylene	0	Q	30-150	
Decachlorobiphenyl	0	Q	30-150	



Lab Number: L1200581

Report Date: 01/19/12

SAMPLE RESULTS

 Lab ID:
 L1200581-17
 D

 Client ID:
 LECSN-2.14

532.72.1

Sample Location: CAMBRIDGE, MA

Matrix: Solid
Analytical Method: 97,8082
Analytical Date: 01/18/12 00:55

Analyst: KB

Project Name:

Project Number:

Percent Solids: Results reported on an 'AS RECEIVED' basis.

130 BISHOP ALLEN DRIVE

Date Collected: 01/10/12 15:15 Date Received: 01/11/12 Field Prep: Not Specified **EPA 3580A** Extraction Method: Extraction Date: 01/17/12 18:30 Cleanup Method1: EPA 3665A 01/17/12 Cleanup Date1: EPA 3660B Cleanup Method2: Cleanup Date2: 01/17/12

Parameter	Result	Qualifier	Units	RL	MDL	Dilution Factor
MCP Polychlorinated Biphenyls	- Westborough Lab					
Aroclor 1016	ND		ug/kg	30000		10
Aroclor 1221	ND		ug/kg	30000		10
Aroclor 1232	ND		ug/kg	30000	, 	10
Aroclor 1242	ND		ug/kg	30000		10
Aroclor 1254	ND		ug/kg	30000	3 44 3	10
Aroclor 1262	ND		ug/kg	10000		10
Aroclor 1268	ND		ug/kg	10000	 .	10

		Acceptance	
% Recovery	Qualifier	Criteria	
0	Q	30-150	
	0 0 0	0 Q 0 Q 0 Q	% Recovery Qualifier Criteria 0 Q 30-150 0 Q 30-150 0 Q 30-150

Project Name: 130 BISHOP ALLEN DRIVE Lab Number: L1200581

Project Number: 532.72.1 Report Date: 01/19/12

SAMPLE RESULTS

Lab ID: L1200581-18
Client ID: LECSN-3.2
Sample Location: CAMBRIDGE, MA

Matrix: Solid
Analytical Method: 97,8082
Analytical Date: 01/18/12 10:05

Analyst: SH

Percent Solids: Results reported on an 'AS RECEIVED' basis.

Date Collected: 01/10/12 14:45 Date Received: 01/11/12 Field Prep: Not Specified Extraction Method: **EPA 3540C** Extraction Date: 01/17/12 13:00 Cleanup Method1: EPA 3665A Cleanup Date1: 01/18/12 Cleanup Method2: EPA 3660B

01/18/12

Cleanup Date2:

Parameter	Result	Qualifier	Units	RL	MDL	Dilution Factor
MCP Polychlorinated Biphenyls	- Westborough Lab					
Aroclor 1016	ND		ug/kg	291		1
Aroclor 1221	ND		ug/kg	291		1
Aroclor 1232	ND		ug/kg	291		1
Aroclor 1242	ND		ug/kg	291		1
Aroclor 1248	ND		ug/kg	194		1
Aroclor 1254	ND		ug/kg	291		1
Aroclor 1260	ND		ug/kg	194		1
Aroclor 1262	ND		ug/kg	97.1	-	1
Aroclor 1268	ND		ug/kg	97.1		1

Surrogate	% Recovery	Qualifier	Acceptance Qualifier Criteria		
2,4,5,6-Tetrachloro-m-xylene	10	Q	30-150		
Decachlorobiphenyl	4	Q	30-150		
2,4,5,6-Tetrachloro-m-xylene	85		30-150		
Decachlorobiphenyl	101		30-150		



01/19/12

Cleanup Date1:

Project Name:130 BISHOP ALLEN DRIVELab Number:L1200581Project Number:532.72.1Report Date:01/19/12

roject Number: 532.72.1 SAMPLE RESULTS

Lab ID: L1200581-19 RE Date Collected: 01/10/12 14:30 Client ID: LECSN-4.12 Date Received: 01/11/12 Sample Location: CAMBRIDGE, MA Field Prep: Not Specified Matrix: Solid Extraction Method: EPA 3540C Analytical Method: 97,8082 Extraction Date: 01/18/12 17:10 Analytical Date: 01/19/12 14:18 Cleanup Method1: EPA 3665A

Analyst: SH
Percent Solids: Results reported on an 'AS RECEIVED' basis.

ercent Solids: Results reported on an 'AS RECEIVED' basis. Cleanup Method2: EPA 3660B Cleanup Date2: 01/19/12

Parameter	Result	Qualifier	Units	RL	MDL	Dilution Factor
MCP Polychlorinated Biphenyls -	Westborough Lab					
Aroclor 1016	ND		ug/kg	300		1
Aroclor 1221	ND		ug/kg	300		1
Aroclor 1232	ND		ug/kg	300		1
Aroclor 1242	ND		ug/kg	300		1
Aroclor 1248	630		ug/kg	200		1
Aroclor 1260	395		ug/kg	200		1
Aroclor 1262	ND		ug/kg	100		1
Aroclor 1268	ND		ug/kg	100		1
Surrogate	% Recovery	Qualifier	Acceptance Criteria			

Surrogate	% Recovery	Qualifier		
	// Recovery	Quanner	Criteria	
2,4,5,6-Tetrachloro-m-xylene	26	Q	30-150	
Decachlorobiphenyl	24	Q	30-150	
2,4,5,6-Tetrachloro-m-xylene	26	Q	30-150	
Decachlorobiphenyl	22	Q	30-150	



Project Name: 130 BISHOP ALLEN DRIVE Lab Number: L1200581

Project Number: 532.72.1 Report Date: 01/19/12

SAMPLE RESULTS

Lab ID: L1200581-20
Client ID: LECSN-5.2
Sample Location: CAMBRIDGE, MA
Matrix: Solid

Matrix: Solid
Analytical Method: 97,8082
Analytical Date: 01/18/12 16:16

Analyst: SH

Percent Solids: Results reported on an 'AS RECEIVED' basis.

Date Collected: 01/10/12 14:00 Date Received: 01/11/12 Field Prep: Not Specified Extraction Method: **EPA 3540C** Extraction Date: 01/13/12 16:30 Cleanup Method1: EPA 3665A Cleanup Date1: 01/17/12 **EPA 3660B** Cleanup Method2:

Cleanup Date2: 01/17/12

Parameter	Result	Qualifier	Units	RL	MDL	Dilution Factor
MCP Polychlorinated Biphenyls	- Westborough Lab					
Aroclor 1016	ND		ug/kg	428		4
Aroclor 1221	ND		ug/kg	428		4
Aroclor 1232	ND		ug/kg	428		4
Aroclor 1242	ND		ug/kg	428	1.00	4
Aroclor 1248	ND		ug/kg	286		4
Aroclor 1254	ND		ug/kg	428		4
Aroclor 1260	ND		ug/kg	286	1944	4
Aroclor 1262	ND		ug/kg	143	19 41	4
Aroclor 1268	ND		ug/kg	143		4

	Acceptance		
% Recovery	Qualifier	Criteria	
16	Q	30-150	
5	Q	30-150	
7	Q	30-150	
7	Q	30-150	
	16 5 7	16 Q 5 Q 7 Q	% Recovery Qualifier Criteria 16 Q 30-150 5 Q 30-150 7 Q 30-150



Lab Number: L1200581 **Project Name:** 130 BISHOP ALLEN DRIVE

Report Date: **Project Number:** 532.72.1 01/19/12

SAMPLE RESULTS

Date Collected: 01/10/12 14:00 Lab ID: L1200581-20 RE Date Received: 01/11/12 Client ID: LECSN-5.2 CAMBRIDGE, MA Field Prep: Not Specified Sample Location: **EPA 3540C** Extraction Method: Matrix: Solid Extraction Date: 01/18/12 17:10 Analytical Method: 97,8082 Cleanup Method1: EPA 3665A Analytical Date: 01/19/12 14:30

SH Cleanup Date1: 01/19/12 Analyst:

EPA 3660B Percent Solids: Results reported on an 'AS RECEIVED' basis. Cleanup Method2:

01/19/12 Cleanup Date2:

Parameter		Result	Qualifier	Units	RL	MDL	Dilution Factor
MCP Polyc	hlorinated Biphenyls - Westbor	ough Lab					
Aroclor 1248		779		ug/kg	78.4		1
Aroclor 1254		888		ug/kg	118	-	1
Aroclor 1260		904		ug/kg	78.4		1
	Surrogate	% Recovery	Qualifier	Acceptance Criteria			
	2,4,5,6-Tetrachloro-m-xylene	33		30-150			
	Decachlorobiphenyl	27	Q	30-150			
	2,4,5,6-Tetrachloro-m-xylene	33		30-150			
	Decachlorobiphenyl	27	Q	30-150			



Project Name: 130 BISHOP ALLEN DRIVE Lab Number: L1200581

Project Number: 532.72.1 Report Date: 01/19/12

SAMPLE RESULTS

D Date Collected: 01/11/12 13:00 Lab ID: L1200581-21 Date Received: 01/11/12 Client ID: LECSS(I)-5.18 Sample Location: CAMBRIDGE, MA Field Prep: Not Specified Extraction Method: EPA 3540C Matrix: Solid 01/13/12 16:30 97,8082 Extraction Date: Analytical Method: EPA 3665A 01/18/12 17:15 Cleanup Method1: Analytical Date:

Analyst: SH Cleanup Date1: 01/17/12

Cleanup Date1: 01/17/12

Percent Solids: Results reported on an 'AS RECEIVED' basis. Cleanup Method2: EPA 3660B Cleanup Date2: 01/17/12

Parameter		Result	Qualifier	Units	RL	MDL	Dilution Factor
MCP Polyc	hlorinated Biphenyls - Westbor	ough Lab					
Aroclor 1254		ND		ug/kg	11800	-	100
	Surrogate	% Recovery	Qualifier	Acceptance Criteria			
	2,4,5,6-Tetrachloro-m-xylene	0	Q	30-150	V		
	Decachlorobiphenyl	0	Q	30-150			
	2,4,5,6-Tetrachloro-m-xylene	0	Q	30-150			
	Decachlorobiphenyl	0	Q	30-150			



Project Name: 130 BISHOP ALLEN DRIVE Lab Number: L1200581

Project Number: 532.72.1 Report Date: 01/19/12

SAMPLE RESULTS

Date Collected: 01/11/12 12:30 Lab ID: L1200581-22 Date Received: 01/11/12 Client ID: LECSW-5.66.1 Sample Location: CAMBRIDGE, MA Field Prep: Not Specified Matrix: Extraction Method: **EPA 3540C** Solid Analytical Method: 97,8082 Extraction Date: 01/13/12 16:30 Cleanup Method1: EPA 3665A Analytical Date: 01/17/12 00:15

Analyst: SH

2,4,5,6-Tetrachloro-m-xylene

Decachlorobiphenyl

Percent Solids: Results reported on an 'AS RECEIVED' basis. Cleanup Method2: EPA 3660B

Cleanup Date2: 01/16/12

01/16/12

Cleanup Date1:

30-150

30-150

Parameter		Result	Qualifier	Units	RL	MDL	Dilution Factor
MCP Polyc	hlorinated Biphenyls - Westbor	ough Lab					
Aroclor 1248		5030		ug/kg	153	744	2
Aroclor 1254		4800		ug/kg	229		2
	Surrogate	% Recovery	Qualifier	Acceptance Criteria			
	2,4,5,6-Tetrachloro-m-xylene	40		30-150			
	Decachlorobiphenyl	326	Q	30-150			

Q

41

273

L1200581

Lab Number:

Report Date: 01/19/12 **Project Number:** 532.72.1

SAMPLE RESULTS

130 BISHOP ALLEN DRIVE

Project Name:

Date Collected:

01/11/12 12:40 D L1200581-23 Lab ID: Date Received: 01/11/12 LECSW-5.66.2 Client ID: Field Prep: Not Specified CAMBRIDGE, MA Sample Location: EPA 3580A Extraction Method:

Matrix: Solid Extraction Date: 01/17/12 18:30 97,8082 Analytical Method: Cleanup Method1: EPA 3665A 01/18/12 12:40 Analytical Date: Cleanup Date1: 01/17/12

KB Analyst: **EPA 3660B** Results reported on an 'AS RECEIVED' basis. Cleanup Method2: Percent Solids:

01/17/12 Cleanup Date2:

Parameter		Result	Qualifier	Units	RL	MDL	Dilution Factor
MCP Polyc	hlorinated Biphenyls - Westbor	ough Lab					
Aroclor 1248		1270000		ug/kg	194000		100
	Surrogate	% Recovery	Qualifier	Acceptance Criteria			
	2,4,5,6-Tetrachloro-m-xylene	0	Q	30-150			
	Decachlorobiphenyl	0	Q	30-150			
	2,4,5,6-Tetrachloro-m-xylene	0	Q	30-150			
	Decachlorobiphenyl	0	Q	30-150			

Lab Number: L1200581

Report Date: 01/19/12

SAMPLE RESULTS

D

Lab ID: L1200581-24
Client ID: LECSW-5.66.3
Sample Location: CAMBRIDGE, MA

532.72.1

Matrix: Solid
Analytical Method: 97,8082
Analytical Date: 01/17/12 14:58

Analyst: SH

Project Name:

Project Number:

Percent Solids: Results reported on an 'AS RECEIVED' basis.

130 BISHOP ALLEN DRIVE

Date Collected: 01/11/12 12:50 Date Received: 01/11/12 Field Prep: Not Specified **EPA 3540C** Extraction Method: **Extraction Date:** 01/13/12 16:30 Cleanup Method1: EPA 3665A Cleanup Date1: 01/16/12 EPA 3660B Cleanup Method2: Cleanup Date2: 01/16/12

Parameter	Result	Qualifier	Units	RL	MDL	Dilution Factor
MCP Polychlorinated Biphenyls	- Westborough Lab					
Aroclor 1248	6870		ug/kg	873		10
Aroclor 1254	10700		ug/kg	1310		10
Surrogate	% Recovery	Qualifier	Acceptance Criteria	•		

Surrogate	% Recovery	Qualifier	Acceptance Criteria	
2,4,5,6-Tetrachloro-m-xylene	0	Q	30-150	
Decachlorobiphenyl	0	Q	30-150	
2,4,5,6-Tetrachloro-m-xylene	0	Q	30-150	
Decachlorobiphenyl	0	Q	30-150	

Cleanup Method2: Cleanup Date2: **EPA 3660B**

01/17/12

Project Name: 130 BISHOP ALLEN DRIVE Lab Number: L1200581

Project Number: 532.72.1 Report Date: 01/19/12

Results reported on an 'AS RECEIVED' basis.

SAMPLE RESULTS

Lab ID: L1200581-25 D Date Collected: 01/11/12 11:30 Client ID: Date Received: 01/11/12 LECSS(I)-4.24 Sample Location: CAMBRIDGE, MA Field Prep: Not Specified **EPA 3580A** Matrix: Solid Extraction Method: 97,8082 Extraction Date: 01/17/12 18:30 Analytical Method: 01/18/12 01:22 Cleanup Method1: EPA 3665A Analytical Date: Cleanup Date1: 01/17/12 Analyst: KB

 Parameter
 Result
 Qualifier
 Units
 RL
 MDL
 Dilution Factor

 MCP Polychlorinated Biphenyls - Westborough Lab

 Aroclor 1254
 88300
 ug/kg
 28800
 - 10

Surrogate	% Recovery	Qualifier	Acceptance Criteria	
2,4,5,6-Tetrachloro-m-xylene	0	Q	30-150	
Decachlorobiphenyl	0	Q	30-150	
2,4,5,6-Tetrachloro-m-xylene	0	Q	30-150	
Decachlorobiphenyl	0	Q	30-150	

Percent Solids:

Project Name: 130 BISHOP ALLEN DRIVE Lab Number: L1200581

Project Number: 532.72.1 Report Date: 01/19/12

SAMPLE RESULTS

Lab ID: L1200581-27 D
Client ID: LECSN(I)-4.4
Sample Location: CAMBRIDGE, MA
Matrix: Solid

Matrix: Solid
Analytical Method: 97,8082
Analytical Date: 01/17/12 13:54

Analyst: SH

Percent Solids: Results reported on an 'AS RECEIVED' basis.

Date Collected: 01/11/12 11:50 Date Received: 01/11/12 Field Prep: Not Specified Extraction Method: EPA 3540C Extraction Date: 01/13/12 16:30 Cleanup Method1: EPA 3665A Cleanup Date1: 01/16/12 Cleanup Method2: EPA 3660B Cleanup Date2: 01/16/12

Parameter	Result	Qualifier	Units	RL	MDL	Dilution Factor
MCP Polychlorinated Biphenyls	- Westborough Lab					
Aroclor 1016	ND		ug/kg	5130		40
Aroclor 1221	ND		ug/kg	5130		40
Aroclor 1232	ND		ug/kg	5130	-	40
Aroclor 1242	ND		ug/kg	5130	-	40
Aroclor 1260	ND		ug/kg	3420	_	40
Aroclor 1262	ND		ug/kg	1710		40
Aroclor 1268	ND		ug/kg	1710		40

		Acceptance	
% Recovery	Qualifier	Criteria	
0	Q	30-150	
	0 0 0	0 Q 0 Q 0 Q	% Recovery Qualifier Criteria 0 Q 30-150 0 Q 30-150 0 Q 30-150



Lab Number: L1200581

Project Number: 532.72.1 Report Date: 01/19/12

SAMPLE RESULTS

130 BISHOP ALLEN DRIVE

Project Name:

Lab ID: D L1200581-28 Client ID: LECSE(I)-4.40 Date Received: Sample Location: CAMBRIDGE, MA Field Prep:

Matrix: Solid 97,8082 Analytical Method: Analytical Date: 01/17/12 12:53 Analyst: SH

Percent Solids: Results reported on an 'AS RECEIVED' basis. Date Collected: 01/11/12 12:00 01/11/12 Not Specified Extraction Method: **EPA 3540C** Extraction Date: 01/13/12 16:30 Cleanup Method1: EPA 3665A Cleanup Date1: 01/16/12 Cleanup Method2: EPA 3660B Cleanup Date2: 01/16/12

Parameter	Result	Qualifier	Units	RL	MDL	Dilution Factor
MCP Polychlorinated Biphenyls	- Westborough Lab					
Aroclor 1016	ND		ug/kg	3900		30
Aroclor 1221	ND		ug/kg	3900		30
Aroclor 1232	ND		ug/kg	3900	-	30
Aroclor 1242	17100	P	ug/kg	3900		30
Aroclor 1248	11900	Р	ug/kg	2600		30
Aroclor 1254	24000	P	ug/kg	3900		30
Aroclor 1260	ND		ug/kg	2600		30
Aroclor 1262	ND		ug/kg	1300		30
Aroclor 1268	ND		ug/kg	1300		30

Surrogate	% Recovery	Qualifier	Acceptance Criteria	A-W-S-101 (VV)
2,4,5,6-Tetrachloro-m-xylene	0	Q	30-150	
Decachlorobiphenyl	0	Q	30-150	
2,4,5,6-Tetrachloro-m-xylene	0	Q	30-150	
Decachlorobiphenyl	0	Q	30-150	



L1200581

01/18/12

Project Name: 130 BISHOP ALLEN DRIVE

BISHOP ALLEN DRIVE Lab Number:

Project Number: 532.72.1 Report Date: 01/19/12

Method Blank Analysis Batch Quality Control

Analytical Method: 97,8082 Analytical Date: 01/18/12 11:47

Analyst: SH

Extraction Method: EPA 3540C
Extraction Date: 01/17/12 13:00
Cleanup Method1: EPA 3665A
Cleanup Date1: 01/18/12
Cleanup Method2: EPA 3660B

Cleanup Date2:

Parameter	Result	Qualifier	Units	RL	6	MDL
MCP Polychlorinated Biphenyls	- Westborough	Lab for sam	ple(s): 1	13,15,18,26	Batch:	WG514054-1
Aroclor 1016	ND		ug/kg	58.7	7	_
Aroclor 1221	ND		ug/kg	58.7	7	
Aroclor 1232	ND		ug/kg	58.7	7	
Aroclor 1242	ND		ug/kg	58.7	7	
Aroclor 1248	ND		ug/kg	39.1	1	
Aroclor 1254	ND		ug/kg	58.7	7	
Aroclor 1260	ND		ug/kg	39.1	1	
Aroclor 1262	ND		ug/kg	19.6	3	
Aroclor 1268	ND		ug/kg	19.6	3	

Surrogate	%Recovery	Qualifier	Criteria	
2,4,5,6-Tetrachloro-m-xylene	127		30-150	
Decachlorobiphenyl	128		30-150	
2,4,5,6-Tetrachloro-m-xylene	116		30-150	
Decachlorobiphenyl	109		30-150	



01/19/12

Project Name: 130 BISHOP ALLEN DRIVE

Project Number: 532.72.1 Lab Number:

L1200581

Report Date:

01/19/12

Method Blank Analysis Batch Quality Control

Analytical Method: Analytical Date:

97,8082

01/19/12 14:42

Analyst:

SH

Extraction Method: EPA 3540C

Extraction Date: Cleanup Method1: EPA 3665A

01/18/12 17:10

Cleanup Date1:

01/19/12

Cleanup Method2: EPA 3660B Cleanup Date2:

01/19/12

ple(s): 19-20 ug/kg ug/kg	Batch: 118 118	-
	10.020	
ug/kg	118	
ug/kg	118	
ug/kg	118	
ug/kg	78.7	#
ug/kg	118	
ug/kg	78.7	TT:
ug/kg	39.4	
ug/kg	39.4	###
	ug/kg ug/kg ug/kg ug/kg ug/kg	ug/kg 118 ug/kg 118 ug/kg 78.7 ug/kg 118 ug/kg 78.7 ug/kg 39.4

		,	Acceptance	
Surrogate	%Recovery	Qualifier	Criteria	
2,4,5,6-Tetrachloro-m-xylene	88		30-150	
Decachlorobiphenyl	83		30-150	
2,4,5,6-Tetrachloro-m-xylene	90		30-150	
Decachlorobiphenyl	92		30-150	



Lab Control Sample Analysis

Batch Quality Control

L1200581 Lab Number:

01/19/12

Report Date:

532.72.1 Project Number:

130 BISHOP ALLEN DRIVE

Project Name:

RPD Limits Qual RPD %Recovery Limits Qual LCSD %Recovery Qual LCS %Recovery Parameter

MCP Polychlorinated Biphenyls - Westborough Lab Associated sample(s): 02-03,07-08,11-12,17,23,25 Batch: WG514287-2 WG514287-3

Aroclor 1016	28	78	40-140	10	30
Amelor 1260	2	7.3	40.440		Ç.

67 Guar	%R
22	
44	

MCP Polychlorinated Biphenyls - Westborough Lab Associated sample(s): 19-20 Batch: WG514309-2 WG514309-3

30	93					
0	4	Acceptance Criteria	30-150	30-150	30-150	30-150
40-140	40-140					
		LCSD **Recovery Qual	91	98	69	93
100	102	Qual				
		LCS %Recovery Qual	92	98	16	93
100	86					
		Surrogate	2,4,5,6-Tetrachloro-m-xylene	Decachlorobiphenyl	2,4,5,6-Tetrachloro-m-xylene	Decachlorobiphenyl
Aroclor 1016	Aroclor 1260					



Certificate/Approval Program Summary

Last revised January 3, 2012 - Westboro Facility

The following list includes only those analytes/methods for which certification/approval is currently held. For a complete listing of analytes for the referenced methods, please contact your Alpha Customer Service Representative.

Connecticut Department of Public Health Certificate/Lab ID: PH-0574. NELAP Accredited Solid Waste/Soil.

Drinking Water (Inorganic Parameters: Color, pH, Turbidity, Conductivity, Alkalinity, Chloride, Free Residual Chlorine, Fluoride, Calcium Hardness, Sulfate, Nitrate, Nitrite, Aluminum, Antimony, Arsenic, Barium, Beryllium, Cadmium, Calcium, Chromium, Copper, Iron, Lead, Magnesium, Manganese, Mercury, Molybdenum, Nickel, Potassium, Selenium, Silver, Sodium, Thallium, Vanadium, Zinc, Total Dissolved Solids, Total Organic Carbon, Total Cyanide, Perchlorate. Organic Parameters: Volatile Organics 524.2, Total Trihalomethanes 524.2, 1,2-Dibromo-3-chloropropane (DBCP), Ethylene Dibromide (EDB), 1,4-Dioxane (Mod 8270). Microbiology Parameters: Total Coliform-MF mEndo (SM9222B), Total Coliform – Colilert (SM9223 P/A), E. Coli. – Colilert (SM9223 P/A), HPC – Pour Plate (SM9215B), Fecal Coliform – MF m-FC (SM9222D))

Wastewater/Non-Potable Water (Inorganic Parameters: Color, pH, Conductivity, Acidity, Alkalinity, Chloride, Total Residual Chlorine, Fluoride, Total Hardness, Silica, Sulfate, Sulfide, Ammonia, Kjeldahl Nitrogen, Nitrate, Nitrite, O-Phosphate, Total Phosphorus, Aluminum, Antimony, Arsenic, Barium, Beryllium, Boron, Cadmium, Calcium, Chromium, Hexavalent Chromium, Cobalt, Copper, Iron, Lead, Magnesium, Manganese, Mercury, Molybdenum, Nickel, Potassium, Selenium, Silver, Sodium, Strontium, Thallium, Tin, Titanium, Vanadium, Zinc, Total Residue (Solids), Total Dissolved Solids, Total Suspended Solids (non-filterable), BOD, CBOD, COD, TOC, Total Cyanide, Phenolics, Foaming Agents (MBAS), Bromide, Oil and Grease. Organic Parameters: PCBs, Organochlorine Pesticides, Technical Chlordane, Toxaphene, 2,4-D, 2,4,5-T, 2,4,5-TP(Silvex), Acid Extractables (Phenols), Benzidines, Phthalate Esters, Nitrosamines, Nitroaromatics & Isophorone, Polynuclear Aromatic Hydrocarbons, Haloethers, Chlorinated Hydrocarbons, Volatile Organics, TPH (HEM/SGT), Extractable Petroleum Hydrocarbons (ETPH), MA-EPH, MA-VPH. Microbiology Parameters: Total Coliform – MF mEndo (SM9222B), Total Coliform – MTF (SM9221B), HPC – Pour Plate (SM9215B), Fecal Coliform – MF m-FC (SM9222D), Fecal Coliform – A-1 Broth (SM9221E).)

Solid Waste/Soil (Inorganic Parameters: pH, Sulfide, Aluminum, Antimony, Arsenic, Barium, Beryllium, Boron, Cadmium, Calcium, Chromium, Hexavalent Chromium, Cobalt, Copper, Iron, Lead, Magnesium, Manganese, Mercury, Molybdenum, Nickel, Potassium, Selenium, Silver, Sodium, Thallium, Tin, Vanadium, Zinc, Total Cyanide, Ignitability, Phenolics, Corrosivity, TCLP Leach (1311), SPLP Leach (1312 metals only), Reactivity. Organic Parameters: PCBs, PCBs in Oil, Organochlorine Pesticides, Technical Chlordane, Toxaphene, Extractable Petroleum Hydrocarbons (ETPH), MA-EPH, MA-VPH, Dicamba, 2,4-D, 2,4,5-T, 2,4,5-TP(Silvex), Volatile Organics, Acid Extractables (Phenols), 3.3'-Dichlorobenzidine, Phthalates, Nitrosamines, Nitroaromatics & Cyclic Ketones, PAHs, Haloethers, Chlorinated Hydrocarbons.)

Maine Department of Human Services Certificate/Lab ID: 2009024.

Drinking Water (Inorganic Parameters: SM9215B, 9222D, 9223B, EPA 180.1, 353.2, SM2130B, 2320B, 2540C, 4500Cl-D, 4500CN-C, 4500CN-E, 4500F-C, 4500H+B, 4500NO3-F, EPA 200.7, EPA 200.8, 245.1, EPA 300.0. Organic Parameters: 504.1, 524.2.)

Wastewater/Non-Potable Water (Inorganic Parameters: EPA 120.1, 1664A, 350.1, 351.1, 353.2, 410.4, 420.1, SM2320B, 2510B, 2540C, 2540D, 426C, 4500Cl-D, 4500Cl-E, 4500CN-C, 4500CN-E, 4500F-B, 4500F-C, 4500H+B, 4500Norg-B, 4500Norg-C, 4500NH3-B, 4500NH3-G, 4500NH3-H, 4500NO3-F, 4500P-B, 4500P-E, 5210B, 5220D, 5310C, 9010B, 9040B, 9030B, 7470A, 7196A, 2340B, EPA 200.7, 6010, 200.8, 6020, 245.1, 1311, 1312, 3005A, Enterolert, 9223D, 9222D. Organic Parameters: 608, 8081, 8082, 8330, 8151A, 624, 8260, 3510C, 3630C, 5030B, MEDRO, ME-GRO, MA-EPH, MA-VPH.)

Solid Waste/Soil (Inorganic Parameters: 9010B, 9012A, 9014A, 9040B, 9045C, 6010B, 7471A, 7196A, 9050A, 1010, 1030, 9065, 1311, 1312, 3005A, 3050B. Organic Parameters: ME-DRO, ME-GRO, MA-EPH, MA-VPH, 8260B, 8270C, 8330, 8151A, 8081A, 8082, 3540C, 3546, 3580A, 3630C, 5030B, 5035.)

Massachusetts Department of Environmental Protection Certificate/Lab ID: M-MA086.

Drinking Water (Inorganic Parameters: (EPA 200.8 for: Sb,As,Ba,Be,Cd,Cr,Cu,Pb,Ni,Se,Tl) (EPA 200.7 for: Ba,Be,Ca,Cd,Cr,Cu,Na,Ni) 245.1, (300.0 for: Nitrate-N, Fluoride, Sulfate); (EPA 353.2 for: Nitrate-N, Nitrite-N); (SM4500NO3-F for: Nitrate-N and Nitrite-N); 4500F-C, 4500CN-CE, EPA 180.1, SM2130B, SM4500Cl-D, 2320B, SM2540C, SM4500H-B. Organic Parameters: (EPA 524.2 for: Trihalomethanes, Volatile Organics); (504.1 for: 1,2-Dibromoethane, 1,2-Dibromo-3-Chloropropane), EPA 332. Microbiology Parameters: SM9215B; ENZ. SUB. SM9223; ColilertQT SM9223B; MF-SM9222D.)

Page Mon-Potable Water (Inorganic Parameters:, (EPA 200.8 for: AI,Sb,As,Be,Cd,Cr,Cu,Pb,Mn,Ni,Se,Ag,TI,Zn); (EPA 200.7 for: AI,Sb,As,Be,Cd,Ca,Cr,Co,Cu,Fe,Pb,Mg,Mn,Mo,Ni,K,Se,Ag,Na,Sr,Ti,TI,V,Zn); 245.1, SM4500H,B, EPA 120.1,

Pennsylvania Department of Environmental Protection Certificate/Lab ID: 68-03671. NELAP Accredited. Drinking Water (Organic Parameters: EPA 524.2, 504.1)

Non-Potable Water (Inorganic Parameters: EPA 1312, 200.7, 410.4, 1664A, SM2540D, 5210B, 5220D, 4500-P,BE. Organic Parameters: EPA 3510C, 3005A, 3630C, 5030B, 625, 624, 608, 8081A, 8081B, 8082, 802A, 8151A, 8260B, 8270C, 8270D, 8330)

Solid & Hazardous Waste (Inorganic Parameters: EPA 350.1, 1010, 1030, 1311, 1312, 3050B, 3060A, 6010B, 6010C, 7196A, 7471A, 9010B, 9012A, 9014, 9040B, 9045C, 9050, 9065, SM 4500NH3-H. Organic Parameters: 3540C, 3546, 3580A, 3630C, 5035, 8015B, 8015C, 8081A, 8081B, 8082, 8082A, 8151A, 8260B, 8270C, 8270D, 8330)

Rhode Island Department of Health Certificate/Lab ID: LAO00065. NELAP Accredited via NY-DOH.

Refer to MA-DEP Certificate for Potable and Non-Potable Water.

Refer to NJ-DEP Certificate for Potable and Non-Potable Water.

Texas Commisson on Environmental Quality Certificate/Lab ID: T104704476-09-1. *NELAP Accredited*. *Non-Potable Water* (Inorganic Parameters: EPA 120.1, 1664, 200.7, 200.8, 245.1, 245.2, 300.0, 350.1, 351.1, 353.2, 410.4, 420.1, 6010, 6020, 7196, 7470, 9040, SM 2120B, 2310B, 2320B, 2510B, 2540B, 2540B, 2540D, 426C, 4500CLE, 4500CN-E, 4500F-C, 4500H+B, 4500NH3-H, 4500NO2B, 4500P-E, 4500 S2 D, 510C, 5210B, 5220D, 5310C, 5540C. Organic Parameters: EPA 608, 624, 625, 8081, 8082, 8151, 8260, 8270, 8330.)

Solid & Hazardous Waste (Inorganic Parameters: EPA 1311, 1312, 9012, 9014, 9040, 9045, 9050, 9065.)

Virginia Division of Consolidated Laboratory Services Certificate/Lab ID: 460195. NELAP Accredited.

Non-Potable Water (Inorganic Parameters: EPA 3005A,3015,1312,6010B,6010C,SM4500S-D, SM4500-CN-CE, Lachat 10-204-00-1-X. Organic Parameters: EPA 8260B)

Solid & Hazardous Waste (Inorganic Parameters: EPA 3050B, 1311, 1312, 6010B, 6010C, 9030B, 9010B, 9012A, 9014. Organic Parameters: EPA 5035, 5030B, 8260B.)

Department of Defense Certificate/Lab ID: L2217.

Drinking Water (Inorganic Parameters: SM 4500H-B. Organic Parameters: EPA 524.2, 504.1.)

Non-Potable Water (Inorganic Parameters: EPA 200.7, 200.8, 6010B, 6020, 245.1, 245.2, 7470A, 9040B, 300.0, 332.0, 6860, 353.2, 410.4, 9060, 1664A, SM 4500CN-E, 4500H-B, 4500NO3-F, 5220D, 5310C, 2320B, 2540C, 3005A, 3015, 9010B, 9056. Organic Parameters: EPA 8260B, 8270C, 8330A, 625, 8082, 8081A, 3510C, 5030B, MassDEP EPH, MassDEP VPH.)

Solid & Hazardous Waste (Inorganic Parameters: EPA 200.7, 6010B, 7471A, 9010, 9012A, 6860, 1311, 1312, 3050B, 7196A, 9010B, 3500-CR-D, 4500CN-CE, 2540G, Organic Parameters: EPA 8260B, 8270C, 8330A/B-prep, 8082, 8081A, 3540C, 3546, 3580A, 5035A, MassDEP EPH, MassDEP VPH.)

The following analytes are not included in our current NELAP/TNI Scope of Accreditation:

EPA 8260B: Freon-113, 1,2,4,5-Tetramethylbenzene, 4-Ethyltoluene. EPA 8330A: PETN, Picric Acid, Nitroglycerine, 2,6-DANT, 2,4-DANT. EPA 8270C: Methyl naphthalene, Dimethyl naphthalene, Total Methylnapthalenes, Total Dimethylnaphthalenes, 1,4-Diphenylhydrazine (Azobenzene). EPA 625: 4-Chloroaniline, 4-Methylphenol. Total Phosphorus in a soil matrix, Chloride in a soil matrix, TKN in a soil matrix, NO2 in a soil matrix, NO3 in a soil matrix, SO4 in a soil matrix.

odd levelad side.								n-2010)	FORM NO: 01-01 (rev. 18-Jen-2010)
30.00	Inlia 1350	W 11	Call hard	1350	1/11/12	1. Shop ha	1 Sham	((
J394-	Date/Time	ed By:	Received By:	Date/Time	Dat	led By:	- 콜	MA MCP or CT RCP?	MA MCP
pletely. Samples can not be logged.			A	Preservative	Pro			ROJECT .	IS YOUR PROJECT
Please print clearly, legibly and com-			A	Container Type	Contr		m	PLEASE ANSWER QUESTIONS ABOVE	PLEASE ANSWE
			*		_	1030	5.4)	10
			*			1160	2.3	1	9
			У.		_	1130	3.12	1	Ç.
			>			1700	2,10	i	4
			×	-		\$536	5	LECSS-	20
			×			1000	5.57	1	5
			У.	-		0845	7.17	1 -	٩
			*		+	0830	3.2	1	3
			×			2160	2.86	- 2	7
			×	STV	Cawlk	र्वा यावार	1.31	Lecse -	008
Sample Specific Comments s	///	1 1 1 1		Initials	warnx	Date Time			(A) 000 001)
(Pleasu specify below)	////	/ / /	ρ _ς [Sampler's	Sample	ollectic	Sample ID	Sam	ALPHA Lab ID
Preservation	/ / /		3 (8			•			
□ Done □ Not needed #		/ / / /	ANA OBZ)	-	oe performed	and what tests MS to samples)	If MS is required, indicate in Sample Specific Comments which samples and what tests MS to be performed. (Note: All CAM methods for inorganic analyses require MS every 20 soil samples)	dicate in Sample Specific hods for inorganic analys	If MS is required, in (Note: All CAM me)
SAMPLE HANDLING	/ / /		LYSI			118/12	zed by Alpha	These samples have been previously analyzed by Alpha	Other Project S
1	-	/////	S	(pproved)	Time:	I NOON long common if pre-approved.	Data Due:	Transport @ 1,50+5 hosens	Email: 1 Conde
Protocols) Required?	able Confidence	Are CT RCP (Reasonable Confidence Protocols) Required?					N Standard	830-3360	Fax:
Are MCP Analytical Methods Required? Is Matrix Spike (MS) Required on this SDG? (If yes see note in Comments)	ethods Required Required on this	Are MCP Analytical Methods Required? Is Matrix Spike (MS) Required on this SI	Yes I No	が		Turn-Around Time	Turn-A	830-3344	9
CT REASONABLE CONFIDENCE PROTO	Y CT REAS	UMPTIVE CERTAINTY	PRES			20	5	4	سرا ل
	0	NA	State /Fed Program		Condon	-1		-	Address: 39
	imits	quirements/Report Limits	Regulatory Req		532.72.1	532.72.1	Project #:	o Gumesai	Client: 1 datship
		□ Add¹ Deliverables	M ADEx		-		Project Location:	on	Client Information
Same as Client info PO#:	Ma Sam	REMAIL	□ FAX	Dave	800 L	ame: 130 Edus Allen	Project Name:	FAX: 508-822-3288	FAX: 508-898-9193
Billing Information		Report Information - Data Deliverables	Report Informa			Project Information	Project	MANSFIELD, MA	WESTBORO, MA
[850217] :# 40°C WHATW	ALP	= <i>d </i>	Date Rec'd in Lab:	2	PAGE		CHAIN OF CUSTODY	CHA	AHEA

aç							
Alpha's Terms and Conditions	es anthu	1				10)	FORM NO: 01-01 (rev. 18-Jan-2010)
All samples submitted are subject to	11.10 /25	Com / human	120	-7a/12	of T. Ships	116 fore	
start until any ambiguities are reschast	Date/Time	Received By:	Date/Time	0	Relinquished By:	1	MA MCP or CT RCP?
pletely. Samples can not be logged		4.	Preservative				IS YOUR PROJECT
		A	Container Type	S		JESTIONS ABOVE	PLEASE ANSWER QUESTIONS ABOVE
						7	
							•
		8	_	7000		LECSE(1) - 4.40	P
		×		1150		LEUSN (;) - 4.4	
		*		1140		LECSW(1)-4.74	48
		*		1130		LECSS(i) - 4.24	28
		8		1250		5.66.3	7
		<i>y</i>		1240		5.66.7	23
		8		1230	-	LECSW- 5.66.1	1
		*	CLN ,	1300 caulk	Value	1-6css(i)-5.18	3 1000
(Pinasa speedly below) Sample Specific Comments S		10/////////////////////////////////////	le Sampler's × Initials	Time Sample	Collection Date Ti	Sample ID	e Only
98		B (
		ANAL 8082	ned.	s: ts MS to be perfon	ts/Detection Limits ch samples and what tes very 20 soil samples)	Office Project Specific Requirements/Comments/Detection Limits: If MS is required, indicate in Sample Specific Comments which samples and what tests MS to be performed. (Note: All CAM methods for inorganic analyses require MS every 20 soil samples)	If MS is required, indic (Note: All CAM methor
SAMPLE HANDLING T		rsis	1.5	Time:	Date Due:	These samples have been previously analyzed by Alpha	These samples have been
Protocols) Required?	Are CT RCP (Reasonable Confidence Protocols) Required?	☐ Yes ■ No Are CTR	(Ipenaulcia-aut	□ RUSH (only confirmed if pre-approved)	Standard D	-3360	=
Are MCP Analytical Methods Required? Is Matrix Spike (MS) Required on this SDG? (If yes see note in Comments)	Are MCP Analytical Methods Required? Is Matrix Spike (MS) Required on this S	© Yes © No Are MCP		е	Turn-Around Time	830-3544	S Fax:
SUMPTIVE CERTAINTY CT REASONABLE CONFIDENCE PROTO	CERTAINTY CT REAS	PPRE	1		ALPHA Quote #:	360	
	Criteria	State /Fed Program MA		1. Condo	Project Manager:	Roud	Address:
	quirements/Report Limits	Regulatory Requirement	3	532.72.10	Project#: 532.	Lightship Engreeing LLC	Client:
PO#	eliverables		cs Low	So Braket Hiller John	2		217: Client Information
	a Deliverables	Report Information - Dat			Project Name:	TEL: 508-822-9300	23 TEL: 508-898-9220 FAX: 508-898-9193
ALPHA Job # 1/200681		Date Rec'd in		PAGE	Project Information	MANAGER D. RA	WESTBORO WA
			2		CUSTO	CHAIN OF CUSTODY	



Technical Data Sheet

QSil214

Specialty Silicone Coating

Product Description

Quantum Silicones' QSil214 is a median viscosity, two-component, addition cure, silicone elastomer.

Key Features

- Medium viscosity
- Fast cure RT cure
- · Low linear shrinkage
- Transparent
- 1:1 A to B mix ratio

Typical Properties

	Uncatalyzed Proper	rties
	"A" Component	"B" Component
Appearance	Transparent	Transparent
Viscosity, cps	4,550	5,200
Specific Gravity	1.00	1.00

Cat	alyzed Properties	
Mix Ratio	1:1	
Pot Life, 25°C	28 minutes	
Cure Time		
	30 min @ 150C	
Durometer	40	
Tensile Strength, psi	650	
Elongation, %	150	
Thermal Conductivity W/mK	0.18	
Refractive Index	1.40	
Useful Temperature Range	-50 to 200C	

Instructions for use

Mixing

Mix equal parts of "A" and "B" and thoroughly by weight or volume. Once the components are mixed the curing process begins. The pot life of the mixed material is shown under typical properties.

De-aeration

Air trapped during mixing should be removed to eliminate voids in the cured product. Vacuum de-airing may be necessary to completely remove all entrapped air bubbles. To insure proper de-airing, subject the mixed material to 29 inches of mercury.

Storage and shelf life

QSil214 should be stored in the original unopened container at 25C (77F). QSil214 will remain useful for a period of 12 months if stored under those conditions.

Not for Product Specification

The technical data listed herein is provided as a reference only and **is not** intended as sales specifications. For sales and technical assistance or for product recommendations, please call 1-800-852-3147.

Quantum Silicones 8021 Reycan Rd Richmond, VA 23237 Phone (804) 271-9010 Fax (804) 271-9055 Customer Service (800)852-3147 www.quantumsilicones.com